



Location E:
Construct a new concrete footpath to link two sections of exiting footpath together.

Location D:
Install a new concrete footpath (reduced radius), and buff tactile paving.

Location C:
Install a new raised un-controlled pedestrian crossing including buff tactile paving.

Location B:
Install 35 retention sockets in front of kerb on the roadway. Install 35 pencil style bollards. The bollards are to be spaced at 2.5m centers approx.

Location F:
Install a thermoplastic/painted mini roundabout (2m diameter) to provide a turning area for school drop offs.

Location A:
Demolish existing raised pedestrian crossing and install new raised crossing with tactiles, ducting, chambers and retention sockets for Zebra Polls

COPYRIGHT:
The design and details shown on this drawing are applicable to their project only and may not be reproduced in whole or in part or be used for any other project or purpose without the written permission of Limerick City and County Council with whom copyright resides.
DO NOT SCALE from this drawing. Use figured dimensions. Contractor to check all dimensions on site prior to commencement of works. Any discrepancies are to be referred to the ARCHITECT.

©Ordnance Survey Ireland/Govt. of Ireland 2021/OSi_NMA_141

REVISIONS

NO.	DATE	REV. BY.	CH.	DESCRIPTION
-	-	-	-	-

DATE	REV. BY.	CH.	DESCRIPTION
-	-	-	-



Comhairle Cathrach & Contae Luimnigh
Limerick City & County Council

Limerick City and County Council
Active Travel
Merchants Quay
Limerick

PROJECT:
Proposed works at Caherdavin.

STAGE:
Section 38

DRAWING TITLE:
General Layout

DATE: 2023	DRAWING NO: 001
SCALE: NTS	
DRAWN: JOC	SHEET SIZE: A3
CHECKED: JOC	REVISION: 0
JOB NO: -	